



CSLB Lic. # A777434 SBE #20916
 DIR #1000001173 WBE #14110042
 23494 Road 196 Lindsay, CA 93247
 Office: 559-562-7802 Fax: 559-562-7902

Proposal

Date	Proposal #
6/19/2019	54576

Adventist Health
 1141 Rose Avenue
 Selma, CA 93662

Adventist Health
 869 N. Cherry
 Tulare, Ca 93274

PO Number	Rep	Project	Job Name			
	NS	Paving	AH03-PV (Tulare Asphalt)			
Description	Qty	U/M	Unit	Rate	Total	
Remove existing concrete path of travel over 495 sq. ft. 6" in depth. Off-haul material from site. Grade and compact existing sub-base material 6" in depth over 495 sq. ft., install new concrete 6" thick with rebar 24" on center. Remove existing asphalt over 15,379 sq. ft. and 437 LF concrete curb, off haul material from site. Grade and compact existing sub-base material 6" in depth over 15,379 sq. ft. Install 437 LF new concrete curb. Install 3" of hot mix asphalt over 15,379 sq. ft., rolled and compacted. Re-stripe all parking lines and symbols. Total for Project				83,399.00	83,399.00	
We look forward to doing business with you.			Total		\$83,399.00	

Any alteration or deviation from the above involving extra costs will only be executed upon written orders for the same, and will become an extra charge over and above the estimate. All agreements must be made in writing. This proposal is only good for 30 days. All material is guaranteed.

ACCEPTANCE OF PROPOSAL

The price, specifications and conditions are satisfactory and hereby accepted. You are authorized to do the work specified. Payment will be made in full upon completion.

Signature _____